Abstract estimate for constructing a Primary School Building for Adikarnataka Colony at Byrapur, Channagiri Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundation and filling in basement, spreading extra carts and including watering and tamping complete ..	C.yd.	0 3 0	17	
2	Stone jelly chunam concrete for foundation and including well tamping complete	C.ft.	0 4 6	121	
3	Size stone in mud for foundation and basement including providing bond stones at every 6′ apart in each course, etc., complete ..	C.ft.	0 4 0	578	
4	Burnt brick in mud for superstructure	„	0 3 6	917	
5	Providing teakwood wrought and put up including wood oiling two coats	„	4 8 0	48·0	
6	Roofing with 1st class Mangalore tiles on T. W. reepers complete	Sqr.	25 0 0	8·34	
7	Ridging with Mangalore ridge tiles in mortar and cement pointing	R.ft.	0 8 0	27¼	
8	Supplying and fixing T. W. doors of the approved design 3½″×4½″ frames with 1¼″ battened shutters and including fixing with necessary hinges, bolts, hooks, padlocks and two coats of chocolate paint, etc., complete	S.ft.	1 4 0	49	
9	Supplying and fixing T. W. windows of the approved design 3½″×4½″ frames with iron bars and battened shutters 1¼″ thick, including fixing with necessary fixtures and two coats of chocolate paint, etc., complete	S.ft.	1 8 0	35	
10	Flooring with Cuddapah slabs or 3″ chunam concrete bed with cement pointing, etc., complete ..	Sqr.	25 0 0	4·5	
11	Supplying and fixing B. S. slabs 6″ thick for pillars, lintels, etc., with grooves and nice dressing, etc., complete	S.ft.	0 8 0	138	
12	Chunam mortar plastering	Sqr.	4 0 0	17¼	
13	White washing two coats	„	0 4 0	17¼	
14	Cement pointing to basement including raking cut joints	„	4 0 0	1·5	
15	Constructing mortar bonds, over roof in brick in mortar and including plastering and white washing, etc., complete	R.ft.	0 2 6	61	
16	Providing T. W. eave board 9″ deep and including two coats of chocolate paint	„	0 8 0	54½	
17	Making a wall board with nice cement plaster in the wall and with black paint, etc., complete ..	L. S.	.. ..	..	
18	Clearing site, levelling ground, etc. ..	„	..	..	

D. A. HUKERI,
Executive Engineer.

ANJANAPUR DIVISION.

Notification dated 2nd December 1939.

Quotations are invited for the purchase of two portable engines of the following description :—

No.	Mys. No.	Make	Condition
1	26	Raboy & Co., Lincoln ..	Not in use for sometime. Requires repairs.
2	115	Clayton & Shuttleworth, Lincoln.	Do do

These are kept in front of the Executive Engineer's Office at Anjanapur and may be examined on any working day. The last date for the receipt of quotations is 25th December 1939.

M. VENKATAKRISHNA RAO,
Executive Engineer.